


Residential **Temporary Rock Construction Exit**

Failure to install the Construction Exit before disturbing the site soils and/or failure to maintain-the Construction Exit will result in enforcement action by the City.



City

5/13 Grove St.

LOT SQ. FOOTAGE = 10,872 33.117.21.31.0037 BUILDING SQ. FOOTAGE = 1,827 DEMO BUILDING COVERAGE = 16.8% 5/13 GROVE

EXISTING ELEVATIONS First Floor 945 Garage Floor Basement Floor Unknow Aprox. Sewer Service Proposed Elev. Existing Elev. Drainage Directions

BENCHMARK,

WORK HOURS:

7:00am to 7:00pm Monday through Friday 9:00am to 6:00pm Saturday NO WORK ON SUNDAY OR HOLIDAYS

> House Side -10 Front-30

Conditions of Demolition/Moving

4' construction fencing shall enclose existing basement perimeter and excavations with slopes steeper than 1:1. Attach fencing to minimum 5' posts buried 1' and spaced at a maximum 10' on center.

Enclose stockpiled soils with properly installed silt fencing.

Property must be restored within thirty (30) days of building demolition/move - utilities abandoned at the property line with a permit, foundation demolished with a separate permit, debris removed, demolition excavation filled to match adjacent grade and seed or sod placed and maintained at disturbed areas OR a permit must be issued for a new structure within thirty (30) days of the building demolition/move.

inch :

T THIS F THE DIRECT OR ENC

nfirm property may be loped prior to demolition

A demolition permit provides no Assurance of permitted future uses

